Build-Out Planning Document

1,600 Sq Ft Laser Hair Removal & Aesthetics Clinic
Lakeland, Florida

Practical master checklist and launch planning guide for taking a leased space from shell or basic lease condition to fully operational clinic.

Use this document as a working build-out checklist, budget map, vendor punch list, and opening readiness tracker. It is intentionally broad so major categories do not get missed during planning, tenant improvement design, permitting, procurement, staffing, and launch.

Important: Florida, Polk County, landlord, insurer, physician-supervision, zoning, building, fire, OSHA, HIPAA, and laser-specific rules should be verified directly with licensed professionals and the relevant authorities before construction and before opening.

Quick-Start Snapshot

- ☐ **Recommended room program:** 1 reception/waiting area, 1 consultation room, 4 treatment rooms, 1 provider workroom/charting area, 1 laundry/utility/storage room, 1 staff break nook, 1 ADA-accessible restroom, 1 back-of-house general storage area.
- ☐ **Lean opening version:** Front desk + waiting, consultation room, 2 treatment rooms, shared provider/workroom, laundry/storage, restroom; leave shell-ready capacity for 1-2 future treatment rooms.
- ☐ **Most common budget pressure points:** Tenant improvements, electrical/HVAC upgrades, cabinetry, laser devices, treatment beds, software subscriptions, signage, inspections, initial supplies, and working capital.
- ☐ **Most common timeline risks:** Permit review, change orders, utility upgrades, long-lead cabinetry/doors/glass, device delivery timing, inspection scheduling, staff hiring, training, and documentation setup.

Recommended Room Program for 1,600 Sq Ft

Planning note: Actual usable room count depends on corridor width, existing plumbing points, storefront geometry, and whether the restroom already exists. The ranges below are practical planning targets, not code approvals.

Area / Room Type	Suggested Count	Typical Size Range	Planning Notes
Reception + waiting	1	180-260 sq ft	Include check-in, retail display, seating, circulation, beverage station, and visual line of sight to entry.
Consultation room	1	70-110 sq ft	Private consults, consent review, skin analysis, photography, and

Area / Room Type	Suggested Count	Typical Size Range	Planning Notes
			financing discussion.
Treatment rooms	3-4	85-120 sq ft each	Laser-focused clinics often function well with 3 rooms at opening and a 4th flex room for growth.
Provider workroom / charting	1	45-80 sq ft	Shared storage, charting, charging station, consumables, and staff touchdown zone.
Laundry / utility	1	35-60 sq ft	Washer/dryer, water supplies, hampers, shelves, utility sink if feasible.
Back storage	1	35-70 sq ft	Bulk supplies, retail overstock, maintenance items, seasonal signage.
Break nook	1	35-70 sq ft	Compact kitchenette, lockers/cubbies, staff meal area if footprint allows.
ADA restroom	1	50-75 sq ft	Verify existing condition, accessibility clearances, grab bars, finishes, and fixture counts with design team.
Circulation / walls / mech	N/A	18%-28% of plan	Do not over-program treatment rooms and forget corridor, ADA turning, mechanical chases, and door swings.

Target planning split for a laser-focused clinic: roughly 55%-65% treatment/consultation revenue space, 15%-20% reception/client circulation, and 20%-25% back-of-house/support.

1. Space Planning & Layout

Reception and Waiting Area

☐ **Check-in visibility:** Position the front desk with a clean line of sight to the entry, waiting area, and corridor entrance to treatment rooms.

☐ **Traffic flow:** Separate client-facing circulation from back-of-house clutter. Clients should not see storage overflow, dirty linen, or open staff prep areas.

☐ **Retail opportunity:** Reserve wall or millwork space for curated retail without overwhelming the room. Keep display lighting flattering and easy to re-merchandise.

☐ **Comfort and acoustics:** Use upholstery and soft surfaces to reduce echo. Conversations at the front desk should not carry deep into the waiting area.

☐ **Power and data:** Plan desk outlets, data drops, receipt printer location, phone charging, POS equipment, camera views, and concealed cable routing.

Consultation Room

☐ **Purpose:** Use for consultations, treatment plan discussions, consent review, photography, financing, and occasional skin analysis or patch testing if appropriate.

☐ **Privacy:** Make this room visually and acoustically private. It often hosts pricing, medical history, and sensitive before-and-after review.

☐ **Furnishings:** Desk or consult table, 2-3 guest chairs, provider chair, monitor or tablet stand, lockable storage, mirror, and strong task lighting.

Treatment Rooms

☐ **Count strategy:** A practical 1,600 sq ft clinic can often support 3 fully active treatment rooms plus a 4th flex room for overflow, future device use, or injectable/facial expansion if legally appropriate.

☐ **Room shape:** Rectangular rooms with a clear side or foot approach to the treatment bed work better than narrow rooms that force staff to pivot around carts.

☐ **Minimum functional clearances:** Preserve circulation around the bed, device parking space, stool movement, and safe cable routing from wall outlets to laser device position.

☐ **Sink strategy:** Determine early whether sinks are needed in each room or if a shared sink strategy is legally and operationally acceptable. This affects plumbing cost materially.

☐ **Consistency:** Make room layouts as standardized as possible so staff can move between rooms without hunting for supplies or switching workflow patterns.

Provider Workroom, Break Area, Restroom, Storage, and Laundry

☐ **Provider workroom:** Use as the operations nerve center for charting, label printing, charging devices, backup stock, forms, and locked storage.

☐ **Break nook:** Even a small staff area improves morale and keeps food and drink out of treatment zones. Include undercounter fridge, microwave, water access, and personal storage if feasible.

☐ **Restroom:** Verify ADA accessibility, finish durability, touchless accessories where desired, and cleaning supply storage. Restroom location should not force clients through back-of-house.

☐ **Storage zones:** Plan separate clean supply, retail overstock, janitorial, and equipment accessory storage rather than one chaotic closet.

☐ **Laundry/utility:** Provide space for washer, dryer, folding surface, detergent storage, dirty/clean linen separation, hampers, and ventilation.

HIPAA and Privacy Considerations in the Layout

☐ **Speech privacy:** Avoid check-in and consult setups where other clients can overhear health history, treatment plans, payment details, or before-and-after discussions.

☐ **Screen privacy:** Position monitors and tablets so protected information is not visible from public seating or corridors.

☐ **Document control:** Design lockable storage for forms, retail receipts containing PHI if applicable, and shredding/recycling stations.

☐ **Photography privacy:** Have a consistent private location for before-and-after photos with neutral backdrop, controlled lighting, and clear consent workflow.

☐ **Sound isolation:** Use insulated walls, solid-core doors where practical, and door bottoms/sweeps if speech transfer becomes a concern.

2. Construction & Build-Out

Core Building Work

☐ **Framing and drywall:** Confirm wall locations with furniture and equipment plans before framing. Add backing in walls for mounted shelves, TVs, dispensers, mirrors, and future accessories.

☐ **Doors:** Use durable commercial doors and hardware. Consider solid-core doors for treatment and consultation rooms to improve privacy.

☐ **Insulation:** Include acoustic insulation in treatment room and consultation room partitions, especially walls shared with waiting or neighboring tenants.

☐ **Flooring:** Prioritize non-porous, durable, easy-clean surfaces with slip resistance and a polished healthcare-adjacent appearance. Avoid flooring that traps dust or is difficult to sanitize.

☐ **Paint and wall finishes:** Choose washable low-sheen commercial coatings. Matte can look upscale but may scuff faster in corridors and treatment rooms.

☐ **Ceilings:** Coordinate ceiling system with lighting, speakers, diffusers, sprinklers, cameras, and access panels. Do not force later rework because devices were not coordinated.

Plumbing and Water

☐ **Sink planning:** Map every handwashing and utility need before drawings are finalized. Late sink additions are expensive.

☐ **Hot water:** Confirm water heater capacity and recovery rate for handwashing, restroom, laundry, and cleaning demands.

☐ **Drain strategy:** Utility sink, restroom, washer box, and any wet-treatment functions should be planned together to minimize costly trenching or rerouting.

☐ **Leak protection:** Use pans, shutoffs, and sensible placement for washer/dryer and under-sink equipment where feasible.

Electrical, Data, and Low Voltage

☐ **Dedicated circuits:** Each major device may require a dedicated circuit or specific amperage/voltage. Obtain electrical specs before final electrical rough-in.

☐ **Outlet placement:** Place standard and dedicated outlets intentionally around treatment bed positions, front desk, consult room, laundry, break area, TVs, printers, and signage.

☐ **Surge and power protection:** Use surge protection, power conditioning where indicated by manufacturer, and battery backup for critical networking and front-desk systems.

☐ **IT/network cabling:** Hardwire front desk, security, phones, printers, and any stationary work areas. Pull extra data runs while walls are open.

☐ **Access control wiring:** Pre-wire entry, rear door, alarm panels, cameras, and door strikes/readers even if full system activation happens later.

HVAC, Ventilation, and Lighting

☐ **Thermal comfort:** Treatment rooms should be comfortable for lightly clothed clients and moving providers. Uneven temperatures become a daily complaint source.

☐ **Ventilation:** Review air changes, return placement, and odor control where topical products, cleaning agents, or laundry heat create stuffiness.

☐ **Humidity and lint:** Laundry areas need sensible ventilation and housekeeping to prevent heat, moisture, and lint accumulation.

☐ **Lighting by zone:** Reception should feel flattering and branded; consult rooms need balanced, color-accurate light; treatment rooms need controllable bright task light plus calming ambient options; back-of-house needs functional brightness.

☐ **Controls:** Install dimmers, switch legs, or scene control where appropriate rather than making every room a single all-or-nothing lighting condition.

Acoustics, Safety, Exterior, and ADA

☐ **Soundproofing:** Prioritize acoustic privacy at consult and treatment rooms, especially if sharing demising walls or if plaza noise is high.

☐ **Signage and storefront:** Coordinate landlord rules, municipal sign permits, hours signage, suite numbering, frosted film, and visibility from parking.

☐ **Security:** Alarm system, glass-break sensors if relevant, monitored cameras, panic strategy for staff, and controlled after-hours access should be planned before finish-out is complete.

☐ **Fire safety:** Coordinate extinguisher locations, exit signage, occupant load, sprinkler alterations if any, and fire alarm modifications with licensed professionals and the AHJ.

☐ **ADA/accessibility:** Verify routes, door clearances, restroom layout, thresholds, turning radii, counter heights, and signage requirements with architect/GC.

3. Furniture, Fixtures & Equipment

Reception / Front Desk

☐ **Desk and check-in millwork:** Reception desk, transaction counter, concealed cable management, locking drawers, keyboard tray if desired, and undercounter storage.

☐ **Front desk equipment:** POS terminal, computer, monitor(s), receipt printer, barcode scanner if retail-heavy, phone handset/headset, label printer, and cash drawer if used.

☐ **Reception accessories:** Literature holders, brochure stand, branded menu display, decorative shelving, charging station, and business card storage.

Waiting Area and Retail

☐ **Seating:** Commercial-grade lounge seating, side tables, wipeable surfaces, and a layout that supports privacy and accessibility.

☐ **Retail fixtures:** Shelving, display towers, under-shelf lighting, tester policy supplies if relevant, and locked storage for backstock.

☐ **Refreshment station:** Water, cups, mini-fridge if used, tray, storage, and daily reset routine.

Treatment and Clinical Support

☐ **Treatment beds/chairs:** Adjustable treatment bed(s), provider stool(s), step stool if needed, bolster pillows, disposable headrest covers, and room-specific linens.

- ☐ **Room support furniture:** Rolling carts, side tables, lockable cabinets, wall mirror, hamper, tissue holder, hooks, and concealed trash/recycling.
- ☐ **Sanitation equipment:** Covered waste bins, sharps containers where applicable, hand sanitizer mounts, wipe dispensers, and designated clean/dirty zones.
- ☐ **Sterilization/sanitation:** If instruments or implements require sterilization or high-level disinfection, plan the proper equipment, workflow, and documentation based on services offered and legal scope.

Back-of-House, Office, and Utility

- ☐ **Laundry:** Commercial-appropriate washer/dryer or robust residential units, sorting bins, shelves, lint management, ironing/steaming if needed.
- ☐ **Break room:** Microwave, compact refrigerator, storage cabinet, coffee setup, table or counter, trash/recycling, and staff cubbies/lockers.
- ☐ **Office:** Admin desk, filing/storage cabinet if any paper records remain, printer/scanner, shred bin, and secure charging area.
- ☐ **Janitorial:** Mop, bucket, vacuum, utility cart, floor cleaner storage, PPE, and wall-mounted cleaning tool organization.

4. Laser Hair Removal & Aesthetic Equipment

Core Device Categories

- ☐ **Primary hair-removal platform:** Select a platform suitable for your intended treatment volume, target skin types, treatment speed goals, service menu, staffing model, and budget.
- ☐ **Secondary treatment capability:** Decide whether opening phase includes only hair removal or also adjacent aesthetics services such as photofacial, pigment, vascular, skin rejuvenation, or skin tightening where lawful and clinically appropriate.
- ☐ **Device room matching:** Assign each major device to a primary room and confirm electrical, cooling, storage, and maneuvering requirements there.

Accessories, Comfort, and Safety

- ☐ **Handpieces and consumables:** Extra tips, distance gauges, treatment windows, gel if required, disposables, foot pedals, cords, and manufacturer-recommended replacement parts.
- ☐ **Cooling and comfort:** Integrated cooling, external cooling device, cooling packs, fans, stress balls, pillows, blankets, and post-treatment soothing supplies.
- ☐ **Eye protection:** Patient and provider eye protection matched to each device or wavelength as required by the manufacturer and safety guidance.
- ☐ **Photography/documentation:** Dedicated camera or high-quality clinic tablet/phone policy, neutral backdrop, ring light or panel light, tripod, measurement guides, and standardized photo angles.

Ownership, Service, and Uptime Planning

- ☐ **Warranty/service contract:** Compare included warranty, loaner policy, response time, preventive maintenance visits, software updates, and consumable lock-in.
- ☐ **Calibration/maintenance planning:** Maintain logs for service calls, preventive maintenance, repairs, calibration/inspection where applicable, and downtime tracking.
- ☐ **Backup workflow:** Have a plan for schedule disruption if a device is down: service contacts, treatment rescheduling SOP, and client communication templates.
- ☐ **Training and credentials:** Document manufacturer training, protocols, medical oversight requirements, contraindication checklists, and competency sign-offs before live treatment.

5. Supplies & Consumables

Treatment Consumables

☐ **Core treatment supplies:** Gloves, gauze, razors, marking pencils, treatment gel if applicable, post-care product, cooling supplies, disposable covers, tissues, cotton rounds, applicators, and wipes.

☐ **Client comfort items:** Blankets, disposable panties/bras if used, headbands, robes, drapes, water cups, and amenity basket items.

☐ **Photo/consent support:** Consent folders, clipboards or tablets, labels, photo backdrop cleanup supplies, and charging cables.

Infection Control and Housekeeping

☐ **Disinfectants:** EPA-appropriate disinfectants for surfaces/equipment per manufacturer compatibility, contact-time charts, and labeled spray bottles where allowed.

☐ **Hand hygiene:** Soap, sanitizer, paper towels, tissues, and hand-care lotion for staff.

☐ **Waste handling:** Liners, covered trash cans, sharps containers if applicable, biohazard supplies if applicable, and pickup/storage arrangements where required.

☐ **Laundry supplies:** Detergent, stain treatment, disinfecting additives if appropriate, hampers, clean/soiled signage, and spare linen sets.

Office, Retail, and Front Desk

☐ **Office supplies:** Paper, labels, receipt rolls, pens, clipboards, printer toner, folders, envelopes, and binder systems for logs/manuals.

☐ **Retail support:** Shopping bags, tissue, shelf talkers, price labels, sample cups/spatulas if used, and tester hygiene supplies.

☐ **Opening order strategy:** Split opening purchase into launch stock, 30-day replenishment stock, and reserve stock so cash is not trapped in excessive inventory.

6. Technology & Software

Core Software Stack

☐ **Practice management / EMR / charting:** Scheduling, charting, intake, treatment notes, photography links, memberships/packages, reminders, deposits, and reporting should live in a system your team will actually use consistently.

☐ **POS and payment processing:** Support in-person payment, card on file, online invoices, financing if offered, package balances, refunds, tips if applicable, and integrated reporting.

☐ **Online booking:** Control what can be self-booked, how long each appointment blocks, lead times, consultation prerequisites, and prepayment/no-show rules.

☐ **Digital forms:** Intake, medical history, consent, privacy notices, treatment-specific protocols, aftercare, cancellation policy, and photography release should be digitized where possible.

☐ **Inventory tracking:** Even a simple inventory system beats guessing. Track retail stock, consumables, reorder points, and device-related consumables separately.

Communications and Infrastructure

☐ **Phone system:** Dedicated business line, call routing, voicemail, text enablement if compliant with your workflow, headset support, and after-hours handling.

☐ **Website and domain:** Branded website, domain, email addresses, online booking link strategy, service pages, FAQ, pricing logic, forms, and SEO basics.

- ☐ **Wi-Fi and cybersecurity:** Separate staff and guest Wi-Fi, strong passwords, multi-factor authentication, firewall/router management, device inventory, and role-based access.
- ☐ **Printer/scanner and office tech:** All-in-one printer/scanner, label printer, document shredder, webcam/headset for tele-consults if used, and battery backup for network gear.
- ☐ **Cloud storage and backups:** Document storage, policy manuals, marketing files, vendor contracts, finance files, and photo backup policy with controlled permissions.

7. Licensing, Compliance & Business Setup

This section is a readiness map, not legal advice. Requirements can vary based on who performs services, physician supervision structure, service mix, property condition, municipality, and insurer expectations. Confirm directly with licensed counsel, accountant, architect/engineer, general contractor, landlord, insurer, and the relevant Florida/local authorities before relying on any item as complete.

Florida and Local Categories to Verify

- ☐ **Business entity and tax setup:** Confirm business formation, EIN, state registration, local tax/accounting setup, sales tax treatment for taxable items if any, and banking/merchant accounts.
- ☐ **Zoning and allowed use:** Before investing in plans or equipment, confirm the intended use is permitted at the Lakeland address and that no special landlord or plaza restrictions apply.
- ☐ **Permits and Certificate of Occupancy:** Tenant improvements usually require permit review, inspections, and final approvals before lawful occupancy/opening. Confirm permit pathway early.
- ☐ **Professional licensing:** Verify the specific licensure and supervision requirements that apply to every service, every provider type, and every device or modality you intend to offer.
- ☐ **Laser/light-based hair removal requirements:** Florida requirements for laser/light-based hair removal, physician supervision, electrology licensure/facility licensure, protocols, and related documentation must be confirmed directly before opening.

Safety, Privacy, and Documentation

- ☐ **OSHA setup:** Hazard communication, SDS access, bloodborne pathogen considerations if applicable, PPE, training records, exposure control documentation if applicable, and workplace incident procedures.
- ☐ **HIPAA/privacy:** Risk assessment, notice/privacy practices as applicable, minimum necessary access, secure device use, breach response planning, and staff confidentiality training.
- ☐ **Biomedical waste and sharps:** If your services generate sharps or biomedical waste, verify generator permit, storage, labeling, pickup, and training requirements.
- ☐ **Policies and manuals:** Prepare employee handbook, SOP manual, emergency procedures, cleaning protocols, incident log, maintenance logs, consent forms, treatment protocols, and complaint resolution process.
- ☐ **Insurance:** General liability, professional liability/malpractice as applicable, property, workers compensation, cyber/privacy, employment practices, business interruption, and equipment coverage.

8. Staffing & Operations Setup

Opening Roles

- ☐ **Clinic owner/operator:** Oversight of vendors, compliance, finance, marketing, culture, and quality control.
- ☐ **Provider(s):** Laser/electrology/aesthetic providers credentialed and trained for the actual service mix at launch.
- ☐ **Front desk / patient coordinator:** Scheduling, phones, check-in, retail, financing/payment collection, follow-up, and review requests.

☐ **Part-time support:** Consider part-time admin, social/content support, or floating clinic assistant rather than overstaffing payroll before demand is proven.

Training and SOPs

☐ **Core training:** Software, intake/consent workflow, room setup/reset, treatment protocols, contraindication screening, photo standards, safety, emergency response, cleaning, and customer service.

☐ **SOP library:** Create written SOPs for consults, pre-treatment, treatment, post-care, no-shows, cancellations, package management, inventory, maintenance, opening, and closing.

☐ **Competency sign-offs:** Use training checklists and sign-off sheets before staff perform independent treatment.

Daily Operations

☐ **Opening procedures:** Alarm/disarm, temperature/music/lighting reset, restroom check, device warm-up, room setup, retail reset, supplies check, and schedule review.

☐ **Closing procedures:** Cashout, chart completion, room turnover, laundry, waste removal, charging devices, locking products, alarm, and next-day prep.

☐ **Cleaning protocols:** Between-client, daily, weekly, and monthly cleaning checklists with ownership assigned.

☐ **Inventory process:** Par levels, reorder points, receiving process, lot/expiry check if applicable, and monthly inventory count.

9. Marketing & Client Experience Setup

Branding in the Space

☐ **Brand assets:** Logo files, color palette, typography, printed signage, treatment menus, digital displays, and brand standards for every physical touchpoint.

☐ **Service presentation:** Clear menu by service category, consultation-first services where appropriate, package/membership explanation, and aftercare handouts.

☐ **Photography-friendly design:** Clean focal wall, flattering mirror area, cohesive finishes, branded but not cluttered décor, and consistent lighting for organic social content.

Client Experience and Growth

☐ **Comfort details:** Blankets, beverage station, phone charging, robes/drapes, calming music, scent policy, and restroom amenities.

☐ **Review generation:** Build a consistent post-visit text/email workflow for reviews, feedback capture, and rebooking.

☐ **Retail merchandising:** Small, intentional assortment displayed cleanly with clear shelf logic, education prompts, and staff talking points.

☐ **Grand opening:** Soft opening plan, referral cards, launch offers, member previews, local partnership outreach, photography, and a day-of operating plan.

10. Budget Framework

Use the template below as a working budget tracker. Mark each line as Must-Have Before Opening, Can Phase In, or Optional Upgrade. Add vendor quotes, deposits due, lead times, and responsible owner as you go.

Category	Line Item	Priority	Estimate	Actual	Notes
Build-out	Architect/design, permitting, GC	Must-have before opening			

Category	Line Item	Priority	Estimate	Actual	Notes
	labor, framing, drywall, electrical, plumbing, HVAC, paint, flooring, doors, millwork, signage				
Furniture & fixtures	Reception desk, seating, mirrors, carts, shelving, stools, storage, break room items	Must-have before opening			
Clinical equipment	Treatment beds/chairs, lighting, sanitation equipment, photography setup, laundry	Must-have before opening			
Laser & device equipment	Primary platform, handpieces, cooling, service plan, shipping/install	Must-have before opening			
Software & tech	EMR/scheduling, POS, phones, website, computers, network, cameras, printer	Must-have before opening			
Compliance & insurance	Licenses, permits, professional fees, policy drafting, insurance	Must-have before opening			

Category	Line Item	Priority	Estimate	Actual	Notes
	premiums				
Supplies & opening inventory	Consumables, linens, retail opening stock, office supplies, housekeeping	Must-have before opening			
Marketing	Branding, print materials, launch campaign, signage, content/photo setup	Can phase in			
Working capital	Payroll buffer, rent, utilities, loan payments, ad spend, contingencies	Must-have before opening			
Optional upgrades	Additional device, upgraded finishes, digital menu boards, premium décor, extra room build-out	Optional upgrade			

Recommended contingency: carry a meaningful tenant-improvement and launch contingency because build-out surprises and launch cash drag are normal, not rare.

11. Opening Timeline

Phase	Typical Focus	Key Dependencies / Notes
1. Pre-lease / immediately after securing space	Zoning/use confirmation, preliminary layout, budget model, funding, landlord work letter review, contractor/design interviews	Do not lock equipment specs or final room counts before confirming what the space and landlord actually allow.
2. Design and due diligence	Measure space, code review,	Device specs, power loads,

Phase	Typical Focus	Key Dependencies / Notes
	reflected ceiling/electrical needs, sink strategy, equipment cut sheets, finish selections	plumbing points, signage constraints, and ADA issues should be known before permit set is finalized.
3. Permitting and bidding	Submit plans, refine contractor scope, solicit bids, place long-lead orders	Permit review can outlast everyone's optimism. Order long-lead doors, glass, cabinetry, and signage only when scope is stable enough.
4. Construction rough-in	Demolition if needed, framing, plumbing, electrical, HVAC, data/low voltage	Do not miss camera, speaker, Wi-Fi, access control, and extra data runs while walls are open.
5. Finishes and fixture install	Drywall finish, paint, flooring, ceilings, lighting, cabinetry, mirrors, doors, storefront, signage	Coordinate final bed placement and device parking so outlet and cabinet conflicts do not appear at punch-out.
6. Equipment, IT, and software setup	Device delivery/install, front-desk hardware, internet, security, phones, software build, forms, photo workflow	Leave time for manufacturer training and tech setup. Delivery windows love to collide with final inspections.
7. Compliance and staffing	Policies/manuals, insurance activation, licensure verification, waste setup if applicable, hiring, onboarding, drills	Staff should train in the actual rooms with the actual devices, supplies, and software.
8. Final inspections and punch list	Municipal finals, CO/occupancy approval as applicable, landlord punch, cleaning, merchandising	Do not announce a hard opening date until approval path and punch-list status are clear.
9. Soft opening	Friends/family models if lawful, limited schedule, workflow debugging, review requests, staff calibration	Soft opening exposes missing supplies, scripting gaps, room reset problems, and software holes before grand-opening traffic arrives.
10. Grand opening and first 30 days	Launch offers, photo/content capture, referral process, KPI review, reorder tuning	Track cancellations, rebook rate, treatment length assumptions, retail conversion, and supply burn closely in month one.

Optional Enhancer A. Phase 1 vs Phase 2 Build-Out Plan

A lean opening can protect cash without making the clinic feel unfinished. The trick is designing Phase 2 capacity during Phase 1, so future expansion is surgical instead of disruptive.

- ☐ **Phase 1 must-have:** Reception, waiting, consultation room, 2 treatment rooms, ADA restroom, compact workroom/laundry, core software, primary device, essential furniture, opening inventory, legal/compliance setup.
- ☐ **Phase 1 future-proofing:** Rough-in extra power/data, pre-plan future cabinetry dimensions, reserve one shell-ready room or flex room, choose finishes and signage scalable to future service additions.
- ☐ **Phase 2 can-phase-in:** Third/fourth treatment room activation, secondary device, upgraded retail display, premium millwork, décor upgrades, photo wall build-out, larger team, expanded service menu.

Optional Enhancer B. Room-by-Room Procurement Checklist

Reception / Waiting

☐ Front desk and transaction counter

☐ 2-6 guest seats depending on layout

☐ Side tables and retail shelving

☐ POS/computer/phone/printer

☐ Brand signage and service menu display

☐ Décor, mirror, charging, refreshment items

Consultation Room

☐ Desk or consult table

☐ 2-3 guest chairs + provider chair

☐ Monitor/tablet stand

☐ Mirror and task lighting

☐ Secure storage

☐ Photo/consent support items

Treatment Room (each)

☐ Treatment bed/chair

☐ Provider stool

☐ Rolling cart

☐ Mirror

☐ Hamper

☐ Trash + sharps if applicable

☐ Disinfectant setup

☐ Eye protection

☐ Room linens/disposables

☐ Small supplies stock

Provider Workroom

☐ Shelving

☐ Locked cabinet

☐ Charging station

☐ Printer/label printer

☐ Back stock bins
☐ Binder/manual station

Laundry / Utility

☐ Washer/dryer
☐ Hampers
☐ Shelves
☐ Detergent and cleaning storage
☐ Folding surface
☐ Utility sink if included

Break Nook

☐ Mini fridge
☐ Microwave
☐ Cabinet or shelving
☐ Table/counter seating
☐ Trash/recycling
☐ Staff cubbies/lockers

Restroom

☐ Soap dispenser
☐ Paper towel or hand dryer
☐ Toilet paper storage
☐ Trash can
☐ Mirror
☐ Amenity basket
☐ Cleaning checklist holder

Master Opening Checklist

☐ Lease fully executed and permitted use confirmed
☐ Final room plan approved by owner, designer, and contractor
☐ Device electrical/plumbing/HVAC requirements incorporated into drawings
☐ Permit applications submitted and tracked
☐ Long-lead items ordered
☐ Insurance broker engaged and coverage bound for opening
☐ Business entity, banking, merchant processing, and bookkeeping live
☐ Professional licensure / supervision / protocols verified for every service and provider
☐ Policies, manuals, logs, forms, and consent packets completed
☐ Software configured: scheduling, charting, payments, forms, reminders, memberships/packages
☐ Internet, phones, Wi-Fi, cameras, alarm, and access control installed
☐ Front desk and treatment room furniture installed
☐ Laser/device(s) delivered, installed, tested, and staff-trained
☐ Opening inventory and consumables received, labeled, and stocked
☐ Laundry, janitorial, and waste processes operational

☐ Restroom stocked and accessible
☐ Retail pricing and merchandising complete
☐ Before-and-after photo setup tested
☐ Cleaning, opening, and closing checklists posted and assigned
☐ Final inspections complete and occupancy/opening approvals received as required
☐ Soft opening completed and workflow issues corrected
☐ Grand opening assets ready: signage, offers, QR codes, review process, content capture plan
☐ Thirty-day working capital reserve available

Missing-Items Risk List: Commonly Overlooked in Med Spa and Laser Clinic Build-Outs

☐ **Device electrical specs obtained too late:** Can force expensive rework or extension cords nobody should be improvising around.
☐ **Insufficient storage:** Clinics rarely regret adding storage during design. They constantly regret skipping it.
☐ **Poor acoustic privacy:** Clients remember overheard conversations more vividly than your paint color.
☐ **No standardized photo workflow:** Inconsistent photos weaken marketing, treatment comparison, and expectation management.
☐ **Underestimating laundry and linen volume:** Aesthetic businesses create more textile chaos than people admit during planning.
☐ **Weak front-desk cable management:** A beautiful reception desk turns into a visible wire swamp fast.
☐ **No contingency budget:** Construction and opening phases treat optimism as prey.
☐ **No backup plan for device downtime:** Lost treatment days can snowball into cancellations, refunds, and review damage.
☐ **Incomplete SOPs and treatment protocols:** Staff make up their own system when yours is not written down.
☐ **Opening before software and forms are truly ready:** Chaos at check-in travels all the way through treatment and checkout.
☐ **Ignoring signage and landlord rules until late:** Storefront visibility and permit timing can delay launch or force redesign.
☐ **Too little working capital:** Opening day is not the finish line; it is the start of carrying payroll, rent, and marketing while demand ramps.

Selected Florida / Lakeland Verification Notes

- Confirm allowed use, planning/zoning compatibility, and local business tax requirements with the City of Lakeland before relying on the site plan or opening assumptions.
- Confirm permit pathway, inspections, and certificate of occupancy or final approval requirements with the local building authority and your contractor/design team.
- Confirm current Florida laser/light-based hair removal licensure, supervision, facility, and protocol requirements directly with the Florida Department of Health / Medical Quality Assurance resources applicable to your service model.
- If sharps or biomedical waste will be generated, confirm Florida biomedical waste permitting/handling requirements with the county health department and state resources before opening.